

## HEADQUARTER RANGE, BANGALORE.

*Notification dated 25th February 1933.*

Notice is hereby given that sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Bangalore, up to 13th March 1933 (2 P.M.) for "Construction of Grain Stores and certain additions and alterations to the existing Building to accommodate Grain crushing machine in Mysore Lancers, Hebbal". An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th May 1933.

2. The plans, detailed estimate and conditions may be seen at the Assistant Engineer's Office, Headquarter Range, Bangalore, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 250 (two hundred and fifty only) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Construction of Grain Stores and certain additions and alterations to the existing Building to accommodate grain crushing machine in Mysore Lancers, Hebbal" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Assistant Engineer, Headquarter Range, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in items of the bond for any short progress or delay. In matters of all disputes about rates, measurements, quality of work, etc., the decision of the Chief Engineer, will be final and legally binding on the contractors.

Abstract estimate of quantities for construction of Grain Stores and making additions and alterations to accommodate grain crushing machine in Mysore Lancers, Hebbal, Bangalore.

| Sl. No.                     | Items of work                                              | Unit  | Quantity | Rate in figures | Rate in words | Amount |
|-----------------------------|------------------------------------------------------------|-------|----------|-----------------|---------------|--------|
| <i>I. New Grain Stores.</i> |                                                            |       |          |                 |               |        |
| 1                           | Earthwork excavation for foundation and filling basement.  | C.yd. | 55       |                 |               |        |
| 2                           | Filling in basement earthwork                              | "     | 15       |                 |               |        |
| 3                           | Burnt stone in clay                                        | C.ft. | 2198     |                 |               |        |
| 4                           | Burnt brick in clay                                        | "     | 3201     |                 |               |        |
| 4a                          | Burnt brick in mortar                                      | "     | 228      |                 |               |        |
| 5                           | Burnt stone slabs 6" thick dressed and fixed               | "     | 510      |                 |               |        |
| 6                           | Burnt stone slabs 6" nicely dressed and fixed.             | S.ft. | 76       |                 |               |        |
| 7                           | Teakwood doors with battened shutters, complete.           | "     | 112      |                 |               |        |
| 8                           | Teakwood windows with iron bars and battened shutters.     | "     | 63       |                 |               |        |
| 9                           | Teakwood ventilators with iron bars and battened shutters. | "     | 84       |                 |               |        |
| 10                          | Cutting groves in slab pillars                             | No.   | 8        |                 |               |        |
| 11                          | Teakwood work wrought and put up with wood oiling.         | C.ft. | 156.55   |                 |               |        |
| 12                          | Roofing with 1st Class Mangalore tiles on teak reapers.    | Sqr.  | 17.76    |                 |               |        |
| 13                          | Ridge tiles set in mortar.                                 | R.ft. | 74       |                 |               |        |
| 14                          | Zinc sheet roofing with required                           | Sqr.  | 7.40     |                 |               |        |

| Sl. No.                                                                             | Items of work                                                                          | Unit     | Quantity | Rate in figures | Rate In words | Amount |
|-------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------|----------|----------|-----------------|---------------|--------|
| 16                                                                                  | White washing ...                                                                      | Sqr.     | 46.41    |                 |               |        |
| 17                                                                                  | Pointing the basement with mortar ..                                                   | "        | 1.80     |                 |               |        |
| 18                                                                                  | Chacolate painting two coats                                                           | "        | 5.18     |                 |               |        |
| 19                                                                                  | Flooring with Cuddapah slabs on 3" concrete bed on cement pointing                     | "        | 13.04    |                 |               |        |
| 20                                                                                  | Skirting the walls with Cuddapah slabs 3' high with cement mortar and cement pointing. | "        | 4.92     |                 |               |        |
| 21                                                                                  | Chunam border over roof ...                                                            | Rft.     | 96       |                 |               |        |
| 22                                                                                  | Teakwood eaves board with painting.                                                    | "        | 244      |                 |               |        |
| 23                                                                                  | Teakwood finials ...                                                                   | Each     | 4        |                 |               |        |
| 24                                                                                  | Teakwood Pendants ...                                                                  | "        | 8        |                 |               |        |
| 25                                                                                  | Clearing site and levelling ground ...                                                 | Lump sum |          |                 |               |        |
| 26                                                                                  | Providing a teakwood gate to entrance with brick work complete.                        | Sft.     | 50       |                 |               |        |
| 27                                                                                  | Providing slab pillars including drilling holes and dressing and fixing in concrete.   | "        | 24       |                 |               |        |
| <i>II. Constructing Compound Walls.</i>                                             |                                                                                        |          |          |                 |               |        |
| 1                                                                                   | Earth work Excavation for foundation—compound wall both sides.                         | C.yd.    | 5        |                 |               |        |
| 2                                                                                   | Burnt stone in clay ...                                                                | C.ft.    | 175      |                 |               |        |
| 3                                                                                   | Burnt Brick in clay ...                                                                | "        | 270      |                 |               |        |
| 4                                                                                   | Plastering with mortar ..                                                              | Sqr.     | 3.60     |                 |               |        |
| 5                                                                                   | Providing bond stones ...                                                              | Each     | 6        |                 |               |        |
| 6                                                                                   | Coping with burnt brick in mortar 1½' thick with plastering.                           | Rft.     | 60       |                 |               |        |
| <i>III. Repairing the existing Building for installing Grain Crushing Machines.</i> |                                                                                        |          |          |                 |               |        |
| 1                                                                                   | Dismantling wall for inserting doors,                                                  | C.ft.    | 78       |                 |               |        |
| 2                                                                                   | Providing teakwood doors with battened shutters, iron works, etc., complete.           | Sft.     | 52       |                 |               |        |
| 3                                                                                   | Chunam plastering ...                                                                  | Sqr      | 2.00     |                 |               |        |
| 4                                                                                   | White washing and other sundry repairs.                                                | L. S.    |          |                 |               |        |

N. NARASIMHA IYENGAR,  
Assistant Engineer.